

**Summary****BARODA U. P. BANK****REGIONAL OFFICE AMETHI AT GAURIGANJ, DISTT. AMETHI**

sno	Description	Section	Amount of Tender
1.	Furnishing works	in digits	
2.	Electrical works	in Digits	
3.	Air Conditioner works	in Digits	
	TOTAL WIHTOUT GST	in Digits	
	GST 18%		
	TOTAL WITH GST		

**Note :-**

1. All materials to be used strictly follow the list of approved materials.
2. Any deviation in the use of materials at site other than approved materials list will not be permitted and the bank may cancel the contract at any time for any such misconduct & colour as per bran manual.
3. The workman ship and quality of work should be of good quality and to be satisfaction level of the bank's architect and bank

TENDER OF FURNISHING WORKS FOR **BARODA U. P. BANK** SITUATED AT REGIONAL OFFICE-  
AMETHI AT GAURI GANJ, DISTT. AMETHI.

**1. FURNISHING WORKS:-**

SNO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	<b>FALSE CEILING:- (Gyp board) / :-</b>				
	Providing and fixing Gypsum false ceiling as per India Gypsum specification for ceiling with drops as per drawing including of providing and fixing G.I. Frame work as per specification of India gypsum at a distance of 2'0"c/c both ways complete with 12.5 mm board and all necessary perimeter channels etc. No extra payment will be made for the cutting of light points, stained glass, cove lighting etc. The measurement will be taken in one level, rate should include the drops also, no extra amount will be paid for the drops. The joints to be properly mended with paper tapes and gypsum compound all complete. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work.	1230.00	SQ.FT.		
1.A	<b>24" x 24" Grid False Ceiling (FINE FISSURED PLANKS):</b> Providing and Fixing False ceiling Grid using hot dipped Galvanized steel sections, exposed surface chemically cleaned capping pre-finished inbaked polyester paint. Main tee of size 3000 x 32 x 24 mm at every 1200mm c/c maximum, 1200mm cross Tee of size 1200 x 27 x 24mm at every 600mm intervals and 600 mm cross Tee of size 600 x 25 x24mm at 1200mm max and 3000 x 19 x 19mm wall angle all around the wall to form grid size of 600mm x600mm. The Main grid to be suspended to the MS frame with 2mm pre-straightened GI wire and GI adjustable clamp and Laying of fibre wool board having Fire rating of 60 min. as per BS 476/23 of 1987, Noise reduction co-eff. (NRC) of 0.50, Light	1050.00	SQ.FT.		

I.B	<b>OLD FALSE CEILING :-</b>  REPAIRING, REFURBISHMENT AND LABOUR CHARGES INCLUDING NAILS, FEVICOAL, POLISH AND NECESSARY SCREWS, DOOR CLOSER, GODREJ LOCK, HANDLE, TOWNER BOLT ETC. REQUIRED AS PER SITE REQUIREMENTS AS PER BRAND MANUAL.  Labour Charges 20% of Rs. 80/- i.e. 16/- per Sq.ft.	796.00	SQ.FT.		
2.	<b>PARTITION</b>				
	Providing and fixing partition in position as per design with 2" x 1.5" Aluminum section finished frame work @ 2'-0" c/c both ways screwed to the floor and ceiling with M.S. Cleats and to be treated with anti termite oil. The measurement will be taken upto the false ceiling visible height in case of full height partition. The frame work will be cladded with 10mm thk comm. Ply both sides and to be finished with approved 1 mm laminate (color with vertical grain) as per design with adhesive. 3" high laminated skirting to be fixed bottom side of the partition. Extra frame work to be fixed for fixing class. In the glazed partition 8 to 10mm thk. Glass with etching and bank logo.				
A	<b>PARTLY GLAZED PARTITION</b>				
I	PARTLY GLAZED R.M. CABIN PARTITION UPTO 9'-0" HT. CUTING, REPAIRING, REFURBISHMENT AND LABOUR CHARGES INCLUDING NAILS, FEVICOAL, POLISH AND NECESSARY SCREWS, DOOR CLOSER, GODREJ LOCK, HANDLE, TOWNER BOLT ETC. REQUIRED AS PER SITE REQUIREMENTS AS PER BRAND MANUAL.  Labour Charges 25% of Rs. 250/- i.e. 62.50 per Sq.ft.	440.00	SQ.FT.		
II	PARTLY GLAZED D.R.M. CABIN PARTITION UPTO 9'-0" HT.  CUTING, REPAIRING, REFURBISHMENT AND LABOUR CHARGES INCLUDING NAILS, FEVICOAL, POLISH AND NECESSARY SCREWS, DOOR CLOSER, GODREJ LOCK, HANDLE, TOWNER BOLT ETC. REQUIRED AS PER SITE REQUIREMENTS AS PER BRAND MANUAL.  Labour Charges 25% of Rs. 250/- i.e. 62.50 per Sq.ft.	230.00	SQ.FT.		

III	PARTLY GLAZED CONFERENCE HALL PARTITION UPTO 9'-0" HT.  CUTING, REPAIRING, REFURBISHMENT AND LABOUR CHARGES INCLUDING NAILS, FEVICOAL, POLISH AND NECESSARY SCREWS, DOOR CLOSER, GODREJ LOCK, HANDLE, TOWNER BOLT ETC. REQUIRED AS PER SITE REQUIREMENTS AS PER BRAND MANUAL.  Labour Charges 25% of Rs. 250/- i.e. 62.50 per Sq.ft.	480.00	SQ.FT.		
IV	PARTLY GLAZED LOW HEIGHT PARTITION UPTO 5'-0' HT.  CUTING, REPAIRING, REFURBISHMENT AND LABOUR CHARGES INCLUDING NAILS, FEVICOAL, POLISH AND NECESSARY SCREWS, DOOR CLOSER, GODREJ LOCK, HANDLE, TOWNER BOLT ETC. REQUIRED AS PER SITE REQUIREMENTS AS PER BRAND MANUAL.  Labour Charges 25% of Rs. 250/- i.e. 62.50 per Sq.ft.	480.00	SQ.FT.		
V	Front Glass in Low Height Counters	0.0	SQ.FT.		
B	<b>BLOCKED PARTITION</b>				
I	BLOCKED PARTITION UPTO 9'-0" HEIGHT FOR RECORD ROOM AND UPS ROOM	350.00	SQ.FT.		
3	<b>DOORS</b>				
	Providing and fixing solid core 38mm solid core flush door finished with lippings in all side with necessary door hinges, cylindrical locks (golden, Godrej), door clouser, door stoppers, etc with a frame work of T.W./ Beech wood size 75mm x 62.5mm with necessary hold fast fixed to the wall/partition. 1 mm laminate to be fixed on both sides duly finished, edges to be finished with wooden lippings. A wooden molding size 1.5" x 2/8" to be provided all along the periferi of the frame work in the both sides. All the wooden area to be duly polished as per specification of the Architect. In case of Partly glazed door 8mm thk etched or plain glass with granular blasting/sand blasting as per design of the Architect to be fixed with necessary moldings.				
I	Flap Door	0.0	Sq.ft.		

3 A	FULLY GLAZED ENT. DOOR WITH ALUMINIUM PARTITION REPAIRING, REFURBISHMENT AND LABOUR CHARGES INCLUDING NAILS, FEVICOAL, POLISH AND NECESSARY SCREWS, DOOR CLOSER, GODREJ LOCK, HANDLE, TOWNER BOLT ETC. REQUIRED AS PER SITE REQUIREMENTS AS PER BRAND MANUAL.  Labour Charges 25% of Rs. 375/- i.e. 93.75 per Sq.ft.	64.00	SQ.FT.		
	FOR CONFERENCE HALL	60.00	SQ.FT.		
4.	RM cabin Table:- 6' x 3' H = 2'-6"  Providing and fixing MANEGER'S TABLE 6'-0"x3'-0"x2'-6" (ht.) and 10mm beveled glass of approved make to be fitted on to p obtain the total height of 2'-6" as per detailed drawing . made up of 19 mm commercial board of approved make the finished with 1 mm thick laminate of approved make and shad as approved as par detailed drawing. Table shall be provided with 3 drawers sliding on telescopic channels with proper locking arrangements and keyboard with telescope channels tabletop shall be finished with 1.0 mm thick laminate of approved shade & quality . The work includes provided and fixing locks , wire manager , spirit polishing of steam beach bending etc. complete in all respects to the entire satisfaction of the architect.  Labour charges Only fittings	1 no.	each		
	DRM Table:- 6' -0"x 3'-0" H = 2'-6"  Labour charges Only fittings	1.00	each		
	CM Table:- 5' -0"x 2'-6" H = 2'-6" Labour charges Only fittings	2.00	each		
	Officer Table:- 4' -6"x 2'-6" H = 2'-6" Labour charges Only fittings	18.00	each		
	Reception Table:- 6' -6"x 2'-6" H = 2'-6" semi circular Labour charges Only fittings	1.00	each		

	Conference table:- 17'1" x 5'-0" <b>CUTING, REPAIRING, REFURBISHMENT AND LABOUR CHARGES INCLUDING NAILS, FEVICOAL, POLISH AND NECESSARY SCREWS, DOOR CLOSER, GODREJ LOCK, HANDLE, TOWNER BOLT ETC. REQUIRED AS PER SITE REQUIREMENTS AS PER BRAND MANUAL.</b>  <b>Labour Charges 25% of Rs. 4000/- i.e. 1000/- per Sq.ft.</b>	46'-0"	Rft		
5.	<b>STORAGE</b>				
	Providing and fixing Full height storage 400mm deep made out of 19mm bwp block board finished with 1.0mm laminate in all exposed areas. The drawers to be made out of 19mm BWP block board in the front cladded with 1.0mm laminate (color, vertical grain). sides to be made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19mm block board and should play on drawer slidign castors on powder coated channels. The necessary locks, handles, etc to be provided. Inside of the unit to be enamel painted in matching tone. All the exposed edges of the boards / plywood's to be covered with wooden lapping / moldings duly polished all complete.				
	<b>Old Low Height storage (2'-6" ht).</b>  <b>Labour charges Only fittings</b>	305.00	SQ.FT.		
	Full height storage (7'-0" ht).	280.00	SQ.FT.		
6.	<b>SUGGESTION BOX</b> Providing and making <b>Suggestion box</b> 1.5'x1'x9" deep)as per design & pattern with 19 mm ply finished exterior surface with 6 mm thick extra clear white painted glass having 4"x1" slots with 3 mm thick S.S. plat pasted with metal adhesive. Rate shall includes all necessary hard wares and locking and side opening arrangements	1 NO.	EACH		
7	<b>NOTICE BOARD (1200x900)</b>  <b>Labour charges Only fittings</b>  Providing & fixing Notice Board the tag board of approved make & design, of size 4'	2 NOS.	EACH		

	X 3', with anodized aluminum boarder/frame type. The board should be 3/4" th. Strow board with belvet type fabric lining of apprd. Colour.				
8.	<b>METER BOX</b>  Providing and fixing Meter Box 400mm deep made out of 19mm bwp block board finished with 1.0mm laminate in all exposed areas. The drawers to be made out of 19mm BWP block board in the front cladded with 1.0mm laminate (color, vertical grain). sides to be made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19mm block board and should play on drawer slidign castors on powder coated channels. The necessary locks, handles, etc to be provided. Inside of the unit to be enamel painted in matching tone. All the exposed edges of the boards / plywood's to be covered with wooden lapping / moldings duly polished all complete.	36.00	SQ.FT.		
9.	<b>Old Vertical blinds</b> <b>Labour charges Only fittings</b>	378.00	SQ.FT.		
10	Providing and fixing paneling on wall. Framing shall consist of Aluminum Section 1"X1.5" (Wall Thickness 2 mm) @ 2'0" C/C. Both ways horizontally and vertically on the wall. This framing <b>would be covered by 1/4" thk. Ply and 10mm thk</b> gypsum board.				
	1. RM Cabin 9'-0" height	200.00	SQ.FT.		
	2. DRM cabin 9'-0" Height	140.00	SQ.FT.		
	3. Conference hall Paneling 9'-0"	480.00	SQ.FT.		
	4. Column Paneling including 3'x 1'-6" size fixing Coloured Lacquered Glass for aesthetic appearance in front of counter with coloured focus light and bank logo (Specifications for all Columns	200.00	SQ.FT.		
	5. Hall Paneling 9'-0" height	980.00	SQ.FT.		

Tender /Fur/BUPB/July -03/2024/442-2023

20.07.2024

11	Old Sofa per seater :- <b>Labour charges Only fittings</b>	23.00	each		
12.	Center Table:- <b>Labour charges Only fittings</b>	3 nos	each		
13.	Shutter Boxing with A.C.P. Frame Work -2"X2"X1.5mm thick Aluminium Tubular section (Horizontal/Vertical)Jindal Make Aluminium Composite Panel-3.0mm thick of approved colour with bonding material	150.00	SQ.FT.		
	TOTAL OF INTERIOR WORKS			Rs.	

*Certified by: -*

**(Ar. Manmeet Singh Bajaj)**  
Regd. Architect.  
**M/s Bajaj & Associates,**  
**Sophia Market, Court Road,**  
**Saharanpur.**



**2. ELECTRICAL WORKS:-**

SNO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	Wiring for light points, fan points, bell points, sockets etc. with 1.5 Sq.mm PVC insulated, 1100 V grade grade copper conductor wires and 1.0 Sq mm copper earth wire and 1.0 Sq mm copper earth wire in concealed/surface using PVC (Heavy)25mm dia conduits, accessories such as bends, tees, saddles, draw boxes, mounting boxes, inner plates, cover plates, ceiling rose etc. (including chase cutting where where ever required) and chromium plated brass screws/rowel plugs etc.. The conduits to be laid in ceiling with proper clamps/wall/floor and filling the chase with cement mortar and finish the same in original form/wooden partition/above false ceiling with proper clamps (wherever required as per standard specification.				
	<b>NOTE:</b> Switches and box and all materials are available only wiring and fittings charges	214.00	Nos		
2.	<b>CIRCUIT WIRING</b> :circuit wiring starting from DB to point control box/switch box using PVC (Heavy) 25mm dia conduits, accessories such as bends, tees, saddles, draw boxes, mounting boxes, inner plates, cover plates, ceiling rose etc. (including chase cutting where ever required) with 2x2.5 sqmm PVC insulated 1100V grade multi-stranded copper conductor wire and 1.5 sqmm PVC insulated earth wire and 1.5sqmm. PVC insulated earth Wire (color code to be used).Identification ferrules at both end to be provided. (Flexible conduit/elbow NOT allowed)	400.00	RMT.		
3.	<b>POWER POINTS</b>				
	Same as serial no. 1, but wiring for 16A 6-Pin socket by using 4 sq mm PVC insulated 1100V grade copper conductor wire with independent 2.5 sqmm earth wire from D.B. to first 1st. Socket and 1st socket to 2nd Socket with 2.5 sqmm and 1.5 sqmm earth wire including providing and fixing of 16A 6-Pin socket with 16A switch				
	1. a) Power point with 4sqmm copper	27.00	EACH		

4.	<b>A.C. POINTS:</b>				
	A.C. points i/c Box, MCB, Socket, Switch i/c 32 C MCB complete Only wiring and fittings	14.00	NOS.		
5.	<b>DISTRIBUTION BOARDS:</b>				
	Supplying, installation, testing and commissioning of DOUBLE DOOR type distribution boards ORIGINAL FACTORY FABRICATED ONLY) of following specifications:				
	<b>A) 4-WAY TPN DB (POWER &amp; AC DB)</b>				
	INCOMER :63A 4P	1 NO.	EACH		
	OUTGOING: 32A SP MCB-6Nos. 25A SP MCB-6 Nos. (FOR SPLIT/WINDOW A.C. & POWER POINTS)				
	<b>B) 4-WAY TPN DB (LIGHT &amp; FAN DB)</b>				
	INCOMER :40A 4P. MCB-1No.	1 NO.	EACH		
	OUTGOING: 10A SP MCB-12Nos.				
	C) Supplying & Fixing of 1 no. 40A DP MCB in 4 way SPN DB ( FOR UPS OUT-PUT AT S/R)	1 NO.	EACH		
	D) 8-way SPN DB with 32A ELCB+D.P. 100mA sensitivity Controlling 6 nos. 10Amp. SP MCB and blanking plates. (FOR UPS OUT- PUT AT HALL)	2 NOS.	EACH		
6.	<b>MAIN L.T. PANEL</b>				
	<b>Full set as above REQUIRE REPAIRING AND REFITTINGS I/C NECESSARY ITEMS</b>	1 NO.	EACH		
	<b>INCOMER:</b> 100A HRC fuse base and bridge with HRC fuses Natural link for three phase four wire system- 1Set				
	100A, 25KA, 4P MCCB -----1 NO.				
	100A 4-P, ON LOAD change over switch-1no.				
	160A capacity aluminum bus-bar with heat shrinkable proper insulation with color coated.				
	Digital ammeter and voltmeter with selector switches.				

	R-Y-B phase indicators with 2A backup HRC fuse.				
	<b>OUTGOING:</b>				
	63A 4-P MCCB, 25KA,-----3Nos.				
	63A 4-P ON LOAD change over switch (FOR SYSTEM ROOM/ATM)-----1No.				
	40A 4-P MCCB, 25KA-----1 No.				
	32A TPN MCB, 25KA-----1No.				
7.	Supplying, installation, testing and commissioning of following light fixtures, fans etc.				
	a) PHILIPS/WIPRO/C.G./HAVELLS Make light fixtures				
	i) S/F of LED 2 X2 Light fixture instead of equal Luminous Led light of Philips by the name of Green Square Led Luminaries on only fittings charges	60.00	NOS		
	i) S/f of down light LED Luminaries with reflector (Havel's/Crompton/Philips) complete With cutting of false ceiling 15 watt LED. only fittings charges	50.00	NOS.		
	ii) LED Strip Light (Cove Light)	500.00	Rft.		
	iii) S/F of LED 4' wide ( patti ) Light fixtures	10	NOS.		
	iv) S/F of LED 2' wide ( patti ) Light fixtures	0	NOS.		
	Vii) Supply & fixing of 4' wide double tube set with 2' length Hanging Iron rod and Box in Banking Hall complete with necessary fixture	0.0	NOS		
	b) CROMPTON GREAVES make fans				
	i) 400mm SDX120 Wall Mounted fan only fittings charges	28	NOS.		
	ii).Ceiling fan	02	Nos.		
	c) CROMPTON/GE-ALOSTHOM make				
	1. 18" Exhaust fans Commercial/ industrial with clamps, bolt/dash fastener by grouting on wall for Banking Hall.	2	NOS		

	2. 12" Exhaust fans with clamps, bolt/dash fastener by grouting on wall for Toilets.	2	NOS		
8.	<b>COMPUTER POINT</b>				
	a. Wiring with sx2.5 sqmm + 1x1/5 sq mm PVC insulated 1100 V grade multistranded copper conductor wires in 2 mm thick PVC conduit from UPSDB to computer point. Each point to have 3 nos 6A -5 Pin modular type sockets, one 6A indicator at below the top of table/counter and controlled by one 16A modular switch at above the table top in wooden partition with all accessories, inner/outer plates, metal box etc. and to be fixed on wooden partitions/by grouting on wall etc. as per the requirement at site.	30	nos		
	b. Supply & fixing of porcelain fuse 63 Amp with neutral	06 no	Nos.		
	c. Cut out 63 AP	06 nos.	Nos		
	d. UPS wiring for UPS	150.00	Mtrs.		
9.	<b>TELEPHONE POINT / DATA CABEL</b>				
a.	Providing/Laying of Cat 6 Cable	700.00	Mt.		
b.	Patch Cord 2 Meter	30	Nos.		
c.	Patch Cord 1Meter	30	Nos.		
d.	I/O box	30	Nos.		
e.	RJ 45 Connector, Tray, Cable Manager and 12 U Rack <u>Note:-</u> All products should be D-Link, Tp Link or equivalent International Quality.	2	Nos.		
10.	Supplying and Fixing of 1x8-port switch for telephone wiring connections.	2	No.		
11.	a) Providing and fixing of following earth station as per IS:3043, with water pouring pipes, GI funnels, masonry brick				

	chamber with CI cover, including excavation & refilling of pit after filling with charcoal, salt and sand, identification of pit as required.				
	i) 600x600x3.15mm Copper Plate Earth Station.	2	No.		
	ii) 50mm dia (16SWG & 7mtr. Length) GI Pipe Earth Station.	2	No.		
	b) Supplying, Laying and terminating of the following tapes/ wires with suitable G.I./copper clamps.				
	i) 25x3mm Copper strip with copper clamps.	60.00	Rmt.		
	ii) 1x8SWG Copper earth wire in PVC conduit inside the Branch.	60.00	Rmt.		
12.	CIRCUIT WIRING FOR POWER SOCKETS & A.C. Wiring				
a.	10 mm FR PVC Copper wire & 2.5 mm insulated copper earth wire in 25 mm dia. 2 mm thick pvc conduit ISI mark.	200.00	Rmt.		
b.	2.5 mm & 1.5 mm insulated copper earth wire in 25 mm dia. 2 mm thick pvc conduit ISI mark.	60.00	Rmt.		
c.	4 x 16 mm + 2 x 6 mm pvc wiring in 25 mm dia conduit for main line.	60.00	Rmt.		
d.	4x4 mm + 1 x 2.5 mm pvc wiring/UPS to MCB in 20 mm dia conduit for pipe.	60.00	Rmt.		
	TOTAL			Rs.	

*Certified by: -*

**(Ar. Manmeet Singh Bajaj)**  
 Regd. Architect.  
**M/s Bajaj & Associates,**  
 Sophia Market, Court Road,  
 Saharanpu

	<b><u>AIR CONDITIONER WORKS BARODA UP BANK REGIONAL OFFICE SITUATED AT GAURI GANJ, DISTT AMETHI .</u></b>  <b>A. AIR CONDITIONER WORKS:-</b>				
S.no	Particulars	qty	Unit	Rate	Amount
1.	Re-installed of Aplit and Cassette A.C. with repairing, gas and other necessary required items Cassette A.C. 2.0 Ton 5 Nos Cassette A.C. 1.5 T 2 nos Split A.C. 1.5 T 4 nos Split A.C. 2.0 Ton 3 nos.	14	Nos		
2	Supply/fixing of stand for external unit of A.C. for Split A.C. 7 nos. and Cassette A.C. 7 Nos.	14	nos		
3	Providing and fixing concealed copper pipe with wire proper insulation i/c cutting and repairing etc. Cassette A.C. 7 nos. & Split A.C. 7 nos. Malaysia & Hitachi) total line	500	Rft.		
4	Providing and Fixing 1" PVC Plumbing Concealed Drain pipe with proper fixing & water proofing i/c cutting and repairing etc. and complete upto drain etc. Cassette A.C. 6 nos & Split A.C. 2 nos	300	Rft.		
	<b>TOTAL SAY</b>				

*Certified by: -*

**(Ar. Manmeet Singh Bajaj)**  
 Regd. Architect.  
**M/s Bajaj & Associates,**  
 Sophia Market, Court Road,  
 Saharanpur

Tender /Fur/BUPB/July -03/2024/442-2023

20.07.2024

## **LIST OF APPROVED AND NOMINATED MANUFACTURERS / SUPPLIERS OF INTERIOR MATERIALS**

S.NO.	MATERIALS	APPROVED BRANDS
1	False Ceiling & Cornices	India Gypsum
2	Grid Ceiling	Armstrong/Gypro/luxelon
3	Wood Frame work: All wood must be well seasoned, free from knots, other defects.	Meranti (seasoned) with two coats of wood preservative
4	Aluminum frame work	Jindal/Indal/Hindalco
5	Wood skirting /mouldings, Lipping /beading	Steam beech/ Mahogany/ Teak wood
6	Commercial Ply wood (6mm,8mm,12mm,19mm)	Century /Green ply/Archid
7	Laminate	Century/Merino/Greenlam/Aica
8	Veneer	Century/Greenlam/ Archid
9	Wood Preservative	STP- Pentaphene pale / Termination Tor(Pidilite)
10	Adhesive	Fevicol SH (Pidilite) / Araldite/SR- 998/Century – SH
11	Door Closer	Dorset/Hettich/Hafele/Godrej
12	Floor Spring	Dorma/ Dorset/Hettich/Godrej
13	Door Lock	Dorset/Golden/ Ozone/Godrej
14	Drawer Lock	Dorset/Golden/Hettich/Godrej
15	Hardware	GKW/Everite
15(a)	Drawer Channel	Hettich/Ebco/HefeLe
16	Hinges	Hettich/Ebco/HefeLe
17	Screws	GKW/ Nettle fold
18	Carpet	Interface/ Shaw
19	Vertical/Roller Blinds	MAC/Vista
20	Sun Control Film	3M
21	Soft Board / Display Board	Jolly board/Western India Plywood
22	Paints	Berger/ Asian/ Nerolac
23	Texture paint	Spectrum/ Oikos/Berger
24	Ceramic Tiles	Nitco/Orient bell/H.R.Johnson
25	Vitrified tiles	Nitco/Orient bell/ H.R.Johnson
26	Glass & Mirror	Modi Guard/ Saint gobain/Ashai
27	Handle	Dorset/HefeLe/ Hettich
28	MDF Boards	Greenpanel max/Century/Action
29	Wooden flooring	Green panel max/Pergo/Armstrong
30	PVC flooring	Armstrong/ Krishna vinyl
31	Sanitary fittings	Toto/ Roca/ Kohler/ Grohe
32	Cement	Grade 43/53 of L&T/A.C.C./Ambuja/Ultratech
33	White Cement	Birla cement/JK cement



34	ACP Panels/Sheets	Alubond/ALU Décor/Alstrong/Alstone
35	Flush door	Sonear/Century/Green
36	AC grill	Air products/omicron/patrawala
37	Melamine polish	MRF/Nerolac
38	Ball Catch	Magnetic (M-2)/ Brass or Equivalent

**NOTE:-**

**1. In case of unavailability of any material of specific make an equivalent make can be used only after a written approval of the Architect / Bank. The preference of make/brand of the material listed above will be decided by the Architect/ Bank. The make/brand of any item will be as mentioned in the drawings issued by the Architect.**

**2. The contractor shall provide samples of all materials mentioned in the list of makes as required by the Architect. A written approval of these samples may be sought prior to commencement of any work. Architect / Bank reserves the right to enquire the genuineness of any material used at site directly from the manufacturer/dealer**

**LIST OF APPROVED AND NOMINATED MANUFACTURERS / SUPPLIERS OF ELECTRICAL MATERIALS**

S.NO.	MATERIALS	APPROVED BRANDS
1	PVC fittings	Polycab/ AKG / Precision
2	Wires – PVC insulated copper	Finolex/Polycab/Havells
3	Cables (armored)	Gloster / Havells/ Polycab
4	A.C Starter, Plug Socket	Crabtree / Northwest/ Legrand
5	Light & Power switch socket	Crabtree / Northwest /Philips
6	Telephone Socket	RJ-11 Crabtree/ Philips/MK
7	DB MCB	Legrand/ Hager/ Schneider
8	MCB	Legrand/ Hager/ Schneider
9	Telephone cable	D-Link / Delton / AMP/Dowel
10	Light fitting	PHILIPS/Wipro/Panasonic
11	Fuse Switch	L&T / Havell's
12	Telephone Connector	Corn
13	Ceiling/ Wall fan	Crompton / Orient / Havells
14	Exhaust fan	Crompton / Orient / Havells
15	P.V.C tape	Steel Greep
16	Call bell	Max
17	Cable Lug	Dowell's
18	Cable gland	Comet/ Gripwel/ Dowel
19	Distribution board	L&T/ABB/Legrand
20	MS conduit	BEC/ Precision/ AKG
21	Starter & single phasing preventer	SEIMENS
22	SPN, TPN, Sheet metal	Havel's / Legrand/ L&T
23	Pipe Metal	M.S Conduit 16 S.W.G
24	Metal Pipe Fittings	Cast iron with thread & inspection cover
25	Pipe PVC (Rigid Conduit)	AKG / Polycab/Precision

26	PVC fitting for Rigid	-Do-
27	PVC Roll Pipe	Super Dalda or equivalent heavy guage
28	PVC Casing & Casing Fittings	Good quality heavy guage (colour white)
29	Lugs	Dowel/Braco/Nettlefold
30	Terminals	Essen/Elmex
31	Burglar alarm	Godrej/ Globe detective
32	E-cat 6 Patch panel	Schneider Electric/ Avaya
33	P.A. System	Bosch/ Ahuja
34	UPS wiring	Crompton/KEI
35	Aluminum ducting sheet	Jindal/ SAIL
36	AC	Blue Star, Daikin, Hitachi
37	Timer	Legrand
38	Cat-6 cable/Cat-6 I/O	D-Link/Molex

**NOTE:-**

1. In case of unavailability of any material of specific make an equivalent make can be used only after a written approval of the Architect / Bank. The preference of make/brand of the material listed above will be decided by the Architect/ Bank. The make/brand of any item will be as mentioned in the drawings issued by the Architect.
2. The contractor shall provide samples of all materials mentioned in the list of makes as required by the Architect. A written approval of these samples may be sought prior to commencement of any work. Architect / Bank reserves the right to enquire the genuineness of any material used at site directly from the manufacturer/dealer.